Immersion Cooling Meets Edge Computing
The Anywhere Data Center!

CarnotJet™
Immersion Cooling Container

Product Data Sheet

Turnkey Solution:
- Includes everything you need to get your servers up and running
- Complete Chiller-free Cooling System including Cooling towers / Dry-coolers
- Power Infrastructure including transformers, breakers, and PDUs
- DCIM & Remote Monitoring Systems
- Fire Suppression and Security

Environmentally Resilient:
- Zero air-flow means container can be sealed for protection from the elements
- Oil protects servers from dust, moisture, oxygen, and hence corrosion
- Eliminates hotspots, improving server life and reliability
- Delivers reliable cooling even beyond 50˚C (122˚F) ambient temperatures
- Proven to survive a magnitude 7 earthquake with no downtime

Rapidly Deployable:
- Less than 10 week lead time, from PO to delivery
- Easily transportable for relocation and temporary deployments

Energy-efficient:
- Average mPUE of 1.03 – 1.15 in virtually any climate
- 10-20% reduction of IT load, due to fan removal

Water-free cooling:
- No facility water loop required
- Uses integrated cooling towers with makeup water or drycooler allowing for zero water use

Cost-effective:
- At ~$2/W of IT load, the Containerized CarnotJet is one of the most cost-effective ways to build a data center, period.

GREEN REVOLUTION COOLING

11525 Stonehollow Drive
Suite A-150
Austin, TX 78758
+1 (512) 692-8003
WWW.GRCOOLING.COM

Technical Specifications

		C20	C40	C53
Length		20'	40'	53'
# of Racks		<4x 42U	<8x 48U	<10x 48U
Height		16-20'		
Width		8'		
Heat Load		10-140 kW per rack		
Final Heat rejection Option		Integrated Open Cooling tower (~1 GPM/kW makeup) Integrated Drycooler (Waterless or Hybrid option) No outside water loop required		
Electrical Connection		200-240 VAC or 400-480 VAC		
Monitoring		Server electrical load and distribution Heat load Coolant pressure Estimated filter life Pump command Operating temperatures Rack temperature Power consumption Liquid levels System health and diagnostic output Container air temperature Container physical access history		
Standard Redundancy	Coolant Pump;	2N		
	Control System;	2N		
	Heat Exchangers;	2N		
	Final Heat Rejection;	N or 2N		
	Comfort Cooling;	N or 2N		
	Fire Detection;	2N (Dry contacts + GRC Monitoring)		
mPUE		1.03-1,15		
Electrical options		Flywheel transfer switch Generator		